

PROJECT QUALITY ASSURANCE REPORT

Project period: Jan – March 2025

1. Executive Summary

A comprehensive review was conducted covering:

- Concrete compressive strength test results
- Material approval register
- Site inspection log records

Reveals significant quality control concerns.

2. Concrete Test Analysis

- Total tests reviewed: 30
- Failed tests: 12
- Failure rate: 40%

Observations:

- Marginal strength failures in M30
- M20 average barely meeting the required value
- High slump variation(75mm – 120mm)
- Poor statistical margin

Risk level: High

3. Material Compliance Review

- Total materials reviewed: 20
- Approved: 13 (65%)
- Pending approvals: 7 (35%)

Critical concerns:

- Unapproved admixtures
- Unapproved coarse aggregates

- Supplier inconsistency

Risk level: Moderate- High

4. Site Execution review

- Total Inspections: 40
- Non-Conformance: 21
- NC Rate: 53%

Highest deviations in:

- Foundation Excavation (75%)
- Rebar fixing (66.67%)
- Formwork (58.3%)

Risk level: High

5. Root Cause Summary

Material:

- Inadequate supplier control
- Lack of traceability

Method:

- No statistical mix design margin
- No strict pre-pour inspection enforcement

Manpower:

- Supervision gaps
 - Weak preventive QA mechanism
-

6. Overall Project Risk

Overall quality risk level is high.

Immediate corrective action required.